G R S App [IX 4]

1942 - 43

File No 90-42

Previous References

Serial Nos 71-72

Later References

GENERAL AND REVENUE SECRETARIAT

Serial Nos 71

Part B for July 43

SUBJECT

Elevation of Sewer line in Basavanagudi, B city

G O No L 169-72 dt 6/7/43

1) The Dir of P H,
2) The C E,
3) The Comptroller,
4) The Jnl Commr, B City

Approves the proposal

Letter no C 81-526 dt 12-5-43 from the DPH

Requesting, in the circumstances stated, approval to the proposal of the Special Officer, Bangalore City Drainage, to connect the drainage of Block ABCD, in Basavangudi to the sewer line in the Tata Silk Farm instead of joining it into the Dutt main no 9 by cutting across the main Ridge as provided in the sd estimate, resulting in a saving of Rs 10,500

The Chief Engineer will be requested unofficially to furnish his remarks in the first instance

A will be due, if appd

Lawley 7/6

3) Cir 4-6-43 L 7/6

Memo:

Forwarded with compliments to the Chief Engineer of Mysore for favour of remarks

By order

for Secretary to Govt

No 877 8/6/43

Returned, with compliments

This may be done with great advantage as proposed by the Special Officer, Bangalore City Drainage

for Secretary to Govt

WD 1140 GPB—50,000—6-11-42 7/6/43

7033/L Deviation of a Sewer Line at Basavaguna

Continuation Sheet — File No / Current No — of 2 — Page

SEPT 1943 GOVT SORE

OFFIC OF T 1 ST R FOR L S & P H Date 24 6 43 N 10461

TYS NC S N 1 943 GEN & REC CTT

Draft GO put up for appl

6/6 JDT

22/6

b) Law dept for 22/6/43

7) May be approved the C-E considers that it will be advantageous

Number 2 5 5

24/6/43.

8) Secy 29/6/43

30/6/43

9) Issue

To The Dy Sec(P) 1/7

The Chief Engr

The Comptroller

The Md Commr Tbs Pdtk

L 169-72 3 6/7/43

Advertise the proposal

30/6/1943

(3 703 1/1

G F No 45]

GOVERNMENT OF MYSORE

T I g m
ph

No C 81-82 L
Encls 2

SECY LAW DEPT
GOVT OF MYSORE

OFFICE OF
DIRECTOR PUBLIC HEALTH
BANGALORE
Date 17th May 1940

To

The Secretary to Government,
Law Department,
Bangalore

Sir

Sub: Connecting the drainage of block 39 to the sewer line in the Vidyaranyapuram Extension Scheme by cutting across the main ridge as provided in the sanctioned estimate for street sewers of Sub-drain 9 in Basavangudi -

Ref: Page 38

I have the honour to state that in the estimate for providing street sewers of Sub-drain 9 & portions of Basavangudi and Avalli sanctioned in G O No. L.77 S-467 L.S.G.-7- dated 27th March 1939 a small area in Basavangudi known as (X Y Z) in the accompanying plan) is to be drained into Sub-drain 9 laid along the east road of Basavangudi

The Special Officer, Bangalore City Drainage Division proposes in his letter No 271 dated 7th May 1940 (copy enclosed) to connect the drainage of block 39 to the sewer line in the Vidyaranyapuram, where a new extension has now been formed, instead of joining it on to Sub-drain 9 by cutting across the main ridge as provided in the sanctioned estimate

The above deviation from the sanctioned alignment will result in a saving of Rs 16,000

I request you to be so good as to obtain and convey approval of Government to the proposed deviation

Rule for order
Ref 2975 - DV KKS

I have the honour to be,
Sir,
Your most obedient servant,
Director of Public Health

Put up the original file stated to have been taken by you

The file mk 143 38 (1147,809) put up

WKS 31/5

Letter No. 571 dated 7th May 1913 from the Special Officer, City Drainage Division, Bangalore, to the Director of Public Health in Mysore, Bangalore

---

Re Street sewers of submain No 9 in Basavan udi

--

I have the honour to state in the sanctioned estimate for providing street sewers of submain No 9 in portions of Basavan udi and Gavi lli, a small area (B"D in Basavan udi (shown in accompanying plan) is provided to be drained in to submain No 9 laid along the east road of Basavanudi To do this, the sanctioned alignment contemplates the cutting of the intervening main which involves very high cutting principally lately in rock to a depth of maximum of about 25 feet The cost as provided in the sanctioned estimate for this portion of the work is Rs 16,300/- in the total sanctioned estimate of Rs 1,76,000/- for laying street sewers of submain No 9

Since this line has to be laid against the heavy natural fall of the ground, the work would involve deep excavation and the construction of deep manholes varying from 14 to 23 feet in depth

A new extension has now been formed in the old Data Silk Farm lands and the layout was provided with underground drainage recently since it is now observed that the natural valley of Channamanahalli for this area of the Data Silk Farm could also be very advantageously utilised for this block B"D sanctioned to be drained into Submain No 9, it is now proposed to connect up the drainage B"D to the sewer line in the Data Silk Farm instead of joining it on to Submain No 9 by cutting across the main road

This would effect considerable savings in earth work and the construction of manholes, in fact, in the whole work, as deep manholes are unnecessary and consequently the pipe lines will be laid at comparatively shallow depth The saving so effected would be as much as Rs 16300/- i e, the whole cost provided in the sanctioned estimate by this change of alignment The main in the Data Silk Farm is also large enough to carry this additional sewage from block B"D also

A plan showing the new proposals marked in red is submitted herewith for information The change in the alignment and the large savings of Rs 16,300/- thereby may kindly be approved

---

PROCEEDINGS OF THE GOVERNMENT [redacted] HIS HIGHNESS THE MAHARAJA OF MYSORE

(5

Read:-

Letter No C 81-826 dated the 17th May 1943, from the Director pf Public Health, requesting in the circumstances stated, approval to the proposal of the Special Officer, Bangalore City Drainage to connect the drainage of block 4 B C.D in Basavangudi to the sewer line in the Tata Silk Farm instead of ~~xxxx~~ joining it on to the sub main No 9 by cutting acr ss the main ridge as provided in the sanctioned estimate resulting in a savings of Rs 16,300/-.

2 Un-official No 871 dated 18th June 1943, from the Chief Engineer of Mysore, Public Works Department on the subject.

ORDER NO L 169-72/m&90-42-72

Dated, Bangalore, the 6th July 1943.

A p p r o v e d

For Secretary to Government,
Law Department

The Director of Public Health in Mysore
" Chief Engineer of Mysore, Public Works Department
" Comptroller to the Government of Mysore
" ~~Commissioner~~ Municipal Commissioner through the President, City Municipal Council. Bangalore.

X 5

G R S App F VI—G 2]

SUBJECT

Diary No of letter replied to

General and Revenue Secretariat

( )

the *194*

Date of issue 6/7 194

Signed by

May this be—

(i) printed ?

(ii) treated as a standing order ?

(iii) published in the Gazette English Part ?

(iv) translated ?

(v) placed at the disposal of the press ?

(vi) published in the Gazette Kannada Part ?

Section ML

File No 90-41

Serial No 72

Proceedings of the Government of His Highness the Maharaja of Mysore

Read— Letter No C 81-826 &
17-5-43 from the D P H
requesting, in the circumstances
stated, approval to the
proposal of the Special Officer
Bangalore city Drainage to
Connect the drainage of Block
ABCD in Basavangudi to the
~~Order thereon—No~~ Sewer line in the Tata Silk Farm
instead of joining it as to the
Sub main no 9 by Cutting
across the main ridge as
provided in the sanctioned
estimate resulting in a
savings of Rs 16,300/—

Wo No 877 Dy 15-6-63 from
the Chief Engr of Mysore
on the Subject

order No 164 ?

Approved

Jan
Secretary to Govt
Mysore 2482

To, The Dir of P W
The Chief Engr of Mysore
The Comptroller to Govt
The Asst Comm, Bangalore
The Distt, concerned, Bijapur

List of Engineers

Yours etc

I am etc,